

INSERTA TEE® FITTINGS


CORRUGATED BELL FOR GRAVITY APPLICATIONS

A. BELL END ACCEPTS CORRUGATED HDPE/PP DUAL WALL PIPE--ADS INC. SPECIFICATIONS IN 4", 6", 8", 10", 12", 15", 18" AND 24" SIZES.

B. CURVATURE VARIES WITH MAINLINE DIAMETERS.

C. SPIGOT END PVC SDR 35, ASTM D3034 DIAMETERS: 4", 6", 8", 10", 12", 15", 18" AND 24"

(CONSULT PIPE MANUFACTURER BEFORE USING THIS FOR SANITARY SEWER APPLICATIONS)



INSERTA TEE SIZE	HOLE DIAMETER
4" (100mm)	4 1/2" (114mm)
6" (150mm)	6 1/2" (165mm)
8" (200mm)	8 3/4" (222mm)
10" (250mm)	10 7/8" (276mm)
12" (300mm)	12 7/8" (327mm)
15" (375mm)	15 13/16" (402mm)
18" (450mm)	19 3/16" (503mm)
24" (600mm)	25 5/16" (643mm)

*ONLY AVAILABLE IN PVC

PART #	PART NAME
1	HUB ADAPTER
2	ADS VALLEY GASKET
3	SECURING CLAMP
4	RUBBER SLEEVE (AVAILABLE IN NITRILE AND EPDM BY SPECIAL ORDER)
4A	UPPER SEGMENT**
4B	LOWER SEGMENT***
4C	REFER TO STD - 1103: WALL THICKNESS CHART

** DISTANCE BETWEEN 4A AND 4B WILL VARY BY PRODUCT TYPE

*** WILL NOT APPEAR ON RUBBER SLEEVES FOR CONCRETE OR CLAY PIPE

MATERIALS
PVC SDR 35 ASTM
(4" AND 6" MADE FROM
PVC SDR 26 ASTM)
BAND SS #301
SCREW SS #305
ASTM F477

NOTE: FOR INSTALLATION INSTRUCTIONS, REFER TO DETAIL STD-1100. FOR PROTRUSION INFORMATION, REFER TO DETAIL STD-1101. FOR HOLE SAW INFORMATION, REFER TO DETAIL ST-1102.

ADVANCED DRAINAGE SYSTEMS, INC. ("ADS") HAS PREPARED THIS DETAIL BASED ON INFORMATION PROVIDED TO ADS. THIS DRAWING IS INTENDED TO DEPICT THE COMPONENTS AS REQUESTED. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEERS RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

INSERTA TEE FITTINGS
CORRUGATED BELL FOR
GRAVITY APPLICATIONS

DRAWING NUMBER STD-1105



4640 TRUEMAN BLVD
HILLIARD, OH 43026

DRAWN BY: HAK
DATE: 02/21/23
OK'S BY: ENG
SCALE: NTS
SHEET: 1