






## NYLOPLAST DRAIN BASIN STANDARD DETAIL FOR 4" - 24" DURASLOT PIPE



### USES FOR DURASLOT BASINS



### 15" - 24" BASIN REDUCER OPTIONS

NYLOPLAST 12" CASTINGS			
GRATE OPTIONS	LOAD RATING	PART #	DRAWING #
STANDARD	MEETS H-20	1299CGS	7001-110-203
SOLID COVER	MEETS H-20	1299CGC	7001-110-204

- 1 - NYLOPLAST 12" FRAMES & SOLID COVERS/GRATES SHALL CONFORM TO ASTM A 536 GRADE 70-50-05 FOR DUCTILE IRON.
- 2 - ADAPTERS FOR DURASLOT CONNECTION RANGE BETWEEN 4"-24". SEE DRAWING NO. 7001-110-275 FOR ADS N-12 BELL INFORMATION.
- 3 - SLOT HEIGHT VARIES DEPENDING ON DESIGN CRITERIA. SLOT HEIGHT CAN RANGE FROM 2.5" TO 36". 15" - 24" BASINS WILL REQUIRE SLOTS TALLER THAN STANDARD 2.5"-6" SLOTS.
- 4 - ENCASE ADAPTER IN CONCRETE TO SEAL CONNECTION BETWEEN ADS DURASLOT PIPE AND NYLOPLAST TEE BODY.
- 5 - RECTANGULAR SLOTS ARE TO BE CUT INTO BELL ON NYLOPLAST TEE DURING THE MANUFACTURING PROCESS TO ALLOW PIPE AND TEE TO FIT PROPERLY.
- 6 - 18" AND 24" REDUCERS ARE A CUSTOM PART. 15" X 12" CONE STYLE REDUCER IS TYPICAL BUT REQUIRES TOP TO BE TRIMMED. BASINS WITH REDUCERS WILL REQUIRE CUSTOM SLOT HEIGHTS.
- 7 - DIMENSIONS ARE FOR REFERENCE ONLY. ACTUAL DIMENSIONS MAY VARY. DIMENSIONS ARE IN INCHES.

THIS PRINT DISCLOSES SUBJECT MATTER IN WHICH NYLOPLAST HAS PROPRIETARY RIGHTS. THE RECEIPT OR POSSESSION OF THIS PRINT DOES NOT CONFER, TRANSFER, OR LICENSE THE USE OF THE DESIGN OR TECHNICAL INFORMATION SHOWN HEREIN REPRODUCTION OF THIS PRINT OR ANY INFORMATION CONTAINED HEREIN, OR MANUFACTURE OF ANY ARTICLE HEREFROM, FOR THE DISCLOSURE TO OTHERS IS FORBIDDEN, EXCEPT BY SPECIFIC WRITTEN PERMISSION FROM NYLOPLAST. ©2007 NYLOPLAST	DRAWN BY	NMH	MATERIAL			3130 VERONA AVE BUFORD, GA 30518 PHN (770) 932-2443 FAX (770) 932-2490 www.nyloplast-us.com			
	DATE	3-27-20							
	APPD BY	NMH	PROJECT NO./NAME		TITLE				
	DATE	3-27-20			12" - 24" DRAIN BASIN STANDARD DETAIL FOR 4" - 24" DURASLOT PIPE				
DWG SIZE	A	SCALE	1:25	SHEET	1 OF 1	DWG NO.	7001-110-572	REV	A