

INSERTA TEE® FITTINGS

IPS/SCH 40 GASKETED BELL GRAVITY APPLICATIONS

A. BELL END ACCEPTS PIPE WITH IPS/SCH 40 OR EQUIVALENT O.D. SPECIFICATION IN 4", 6", 8", 10" AND 12" SIZES.

B. CURVATURE VARIES WITH MAINLINE DIAMETERS.


C. SPIGOT END PVC SDR 35, ASTM D3034 DIAMETERS: 2", 3", 4", 6", 8", 10" AND 12" (2" AND 3" MADE FROM IPS/SCH 40, ASTM D1785)

PART #	PART NAME
1	HUB ADAPTOR
2	RUBBER GASKET
3	SECURING CLAMP*
4	RUBBER SLEEVE (AVAILABLE IN NITRILE AND EPDM BY SPECIAL ORDER)
4A	UPPER SEGMENT**
4B	LOWER SEGMENT***
4C	REFER TO STD - 1103: WALL THICKNESS CHART

* OPTIONAL: #316 STAINLESS STEEL BAND, SCREW, AND HOUSING

** DISTANCE BETWEEN 4A AND 4B WILL VARY BY PRODUCT TYPE

*** WILL NOT APPEAR ON RUBBER SLEEVES FOR CONCRETE OR CLAY PIPE



MATERIALS

SDR 26 HWS ASTM D3034
(2" AND 3" MADE FROM
IPS/SCH 40, ASTM D1785)

ASTM F477

BAND SS#301

SCREW SS #305

HOUSING SS #301

INSERTA TEE SIZE	HOLE DIAMETER
2" (50mm)	2 5/8" (67mm)
3" (75mm)	3 3/4" (95mm)
4" (100mm)	4 1/2" (114mm)
6" (150mm)	6 1/2" (165mm)
8" (200mm)	8 3/4" (222mm)
10" (250mm)	10 7/8" (276mm)
12" (300mm)	12 7/8" (327mm)

NOTE: FOR INSTALLATION INSTRUCTIONS, REFER TO DETAIL STD-1100. FOR PROTRUSION INFORMATION, REFER TO DETAIL STD-1101. FOR HOLE SAW INFORMATION, REFER TO DETAIL ST-1102.

ADVANCED DRAINAGE SYSTEMS, INC. ("ADS") HAS PREPARED THIS DETAIL BASED ON INFORMATION PROVIDED TO ADS. THIS DRAWING IS INTENDED TO DEPICT THE COMPONENTS AS REQUESTED. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEERS RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

INSERTA TEE FITTINGS IPS/SCH 40 GASKETED BELL FOR GRAVITY APPLICATIONS

DRAWING NUMBER STD-1108



4640 TRUEMAN BLVD
HILLIARD, OH 43026

DRAWN BY: HAK
DATE: 03/06/23
OK'S BY: ENG
SCALE: NTS
SHEET: 1