


ADAPTER SIZE	48" HP MH
4" - 4"	17°
4" - 6"	19°
4" - 8"	22°
4" - 10"	24°
4" - 12"	26°
4" - 15"	30°
4" - 18"	34°
4" - 24"	42°
4" - 30"	51°
4" - 36"	61°
6" - 6"	22°
6" - 8"	24°
6" - 10"	26°
6" - 12"	29°
6" - 15"	33°
6" - 18"	36°
6" - 24"	44°
6" - 30"	53°
6" - 36"	63°
8" - 8"	26°
8" - 10"	29°
8" - 12"	31°
8" - 15"	35°
8" - 18"	39°
8" - 24"	47°
8" - 30"	55°
8" - 36"	65°

ADAPTER SIZE	48" HP MH
10" - 10"	31°
10" - 12"	34°
10" - 15"	37°
10" - 18"	41°
10" - 24"	49°
10" - 30"	58°
10" - 36"	68°
12" - 12"	43°
12" - 15"	47°
12" - 18"	51°
12" - 24"	66°
12" - 30"	75°
12" - 36"	85°
15" - 15"	51°
15" - 18"	55°
15" - 24"	70°
15" - 30"	78°
15" - 36"	88°
18" - 18"	58°
18" - 24"	74°
18" - 30"	82°
18" - 36"	92°
24" - 24"	81°
24" - 30"	90°
24" - 36"	100°
30" - 30"	99°
30" - 36"	109°
36" - 36"	119°

1. MEASURE THE ANGLE BETWEEN THE PIPE RUNS DIRECTLY FROM THE STORM DRAIN PLANS FOR EACH STRUCTURE LOCATION . THE ANGLE BETWEEN EVERY PIPE RUN MUST BE MEASURED.
2. REFER TO DRAWING NO. 7001-110-012 FOR MINIMUM ANGLE REQUIREMENTS. THE ANGLES LISTED ARE THE MINIMUM ANGLES POSSIBLE BETWEEN ADAPTERS DUE TO PRODUCTION RESTRICTIONS.
3. WHEN RECORDING THE MEASURED ANGLES ON AN ORDER FORM BE SURE TO MEASURE THE ANGLES IN A CLOCKWISE DIRECTION & LABEL THE ANGLE POSITIONS STARTING WITH 0° AT THE TOP OF THE PAGE, THE 12 O'CLOCK POSITION; 90° WOULD THEN FOLLOW AT 3 O'CLOCK, 180° AT 6 O'CLOCK, & SO FORTH (TYPICALLY YOUR OUTLET PIPE WOULD BE LABELED AT 0°).



POLYPROPYLENE BASIN TOP VIEW
WITH REDUCING PLATE, FRAME & GRATE

EXAMPLE:
THE 48" POLYPROPYLENE BASIN ABOVE HAS THREE PIPE STUBS:
18" ADS HP DUAL WALL ADAPTER @ 0°
18" ADS HP DUAL WALL ADAPTER @ 143°
18" ADS HP DUAL WALL ADAPTER @ 292°

ACCORDING TO THE MINIMUM ANGLE CHART A 48" POLYPROPYLENE BASIN REQUIRES A MINIMUM OF 68° BETWEEN AN 18" & 18" STUB. STUB 2 EXCEEDS THE MINIMUM ANGLES BETWEEN STUB 1 AND STUB 3 AND MEETS THE MINIMUM ANGLE REQUIREMENTS. STUB 3 IS 68° FROM STUB 1 AND THEREFORE IS AT THE MINIMUM ALLOWED ANGLE BETWEEN THE TWO ADAPTER SIZES.

ADVANCED DRAINAGE SYSTEMS, INC. ("ADS") HAS PREPARED THIS DETAIL BASED ON INFORMATION PROVIDED TO ADS. THIS DRAWING IS INTENDED TO DEPICT THE COMPONENTS AS REQUESTED. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEERS RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

STANDARD DETAIL
48" POLYPROPYLENE BASIN
MINIMUM ANGLE CHART

DRAWING NUMBER 7009-110-028 A



4640 TRUEMAN BLVD
HILLIARD, OH 43026

DRAWN BY: NMH
DATE: 8/10/23
OK'S BY:
SCALE: NTS
SHEET: 1 OF 1